



3348 Route 208, Campbell Hall, NY 10916
 Phone: 845-496-1600 Fax: 845-496-1398
 12960 Commerce Lake Drive, A14, Fort Myers, FL 33913
 42 Day Farm Road, West Stockbridge, MA 01266
 1813 State Route 7, Harpursville, NY 13787

Client:	Aden Aggregates	Project:	Montgomery Yard QC 2025
Material:	Screened Clay	Project Number:	250360
Source:	Montgomery Quarry	Lab Number:	25-1284
Location:	Stockpile	Item Number:	No Specifications
Date Sampled:	9/19/2025	Sampled By:	Client
Date Tested:	9/29/2025	Tested By:	Michael D Thomas

Report of Triaxial Permeability Test Using Back Pressure
Test Method: ASTM D5084

Proctor Test Data	
ASTM Proctor Test Method:	D698
Maximum Dry Density, PCF:	128.1
Optimum Moisture Content, Percent of Dry Weight:	11.1

Sample Preparation Method:
Chopped to pass 3/8-inch sieve. Compacted in 1-inch lifts, scarified between lifts. □

Test Sample Dimensions	Before Test	After Test
Height, cm:	7.49	7.51
Diameter, cm:	7.27	7.23
Moisture Content, %:	11.01	11.96
Dry Density, PCF:	124.59	125.73

Permeability Test Conditions	
Type of Water Used:	Tap
Maximum Back Pressure, PSI:	79.9
Hydraulic Gradient:	47.6
Effective Stress, PSI (min):	10
Effective Stress, PSI (max):	15.06
Initial Degree of Saturation, %:	87.0
Final Degree of Saturation, %:	98.1

Specific Gravity = 2.67

Permeability Test Results

Coefficient of Permeability @ 20⁰C (68⁰F): **3.20E-08** cm/sec
 Specification:

Comments:

Emily J. Rodriguez

Report Reviewed By: _____

The simple acceptance/rejection decision rule is utilized to determine in-tolerance and out of tolerance or pass/fail conditions and no measurement of uncertainty is applied in this determination.

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc. The results in this report relate only to the items inspected or tested.